Village of Whitehouse, Ohio

Wabash Cannonball Trail Interceptor Sewer & Finzel Road Pump Station Rehabilitation

ADDENDUM 2

October 28, 2020

Planholders of the Village of Whitehouse, Wabash Cannonball Trail Interceptor Sewer & Finzel Road Pump Station Rehabilitation are hereby notified of the following amendments to the Contract Documents. This Addendum is hereby made a part of the Contract Documents.

REFERENCE NOTES

The following are changes to the bidding schedule:

- Sealed Bids for Wabash Cannonball Trail Interceptor Sewer, will be received by the Village of Whitehouse, at the 6925 Providence Street P.O. Box 2476, Whitehouse, Ohio 43571, until 11:00 AM, local time, on November 11, 2020, at which time they will be publicly opened and read.
- All questions shall be submitted by e-mail to Theodore Bennett, P.E. at Jones & Henry Engineers, Ltd. at 3103 Executive Parkway, Suite 300, Toledo, OH 43606, tbennett@jheng.com, no later than 11:00 AM on November 5, 2020 in order to receive a response.

Bidders are reminded to review the required documentation to be submitted with the bid summarized in the Instructions to Bidders.

BID FORM

Replace *Bid Item 2aa* description "*18-inch Storm Sewer, Type C*" with "*18-inch Storm Sewer, Type B*".

SPECIFICATIONS

Page 01010-5, 2.03

Replace *Bid Item 2aa* description "*18-inch Storm Sewer, Type C*" with "*18-inch Storm Sewer, Type B*".

Page 02555-2, 2.04

Replace "***RESERVED***" with the following paragraph:

"2.04 POLYETHYLENE ENCASEMENT FOR DUCTILE IRON PIPE

Buried ductile iron pipe shall be encased in a loose wrapping of polyethylene film at the time of installation. The polyethylene material and method of installation shall meet the requirements of AWWA C105/A21.5."

DRAWINGS

Sheet G-3 – General Summary

Replace *Bid Item 2aa* description "*18-inch Storm Sewer, Type C*" with "*18-inch Storm Sewer, Type B*".

QUESTIONS

The following questions were submitted to the engineer. The answers provided below are for the clarification of the Bidders' questions.

Question #6 – Do the existing force mains need to grouted or just plugged?

Abandoned force main on the plan and profile sheets are to just be cut and capped. Refer to details on sheet SA-0.2. Piping to be cut and filled with CDF can be found on sheet SA-0.5 and SA-0.7.

Question #7 – Is detectable warning tape required for the gravity sewer?

Detectable warning tape is not required for the gravity sewer.

Question #8 – Do manhole quantities reflect the 1 VLF added for the base?

See Specification Section 01010, 5.04, A.

Question #9 – Is polyethylene encasement required on ductile iron pipe?

Yes, See Addendum 1. Polyethylene encasement is required on ductile iron pipe, but not for bored casing ductile iron pipe.

Question #10 – Do the DBE forms need to be submitted with the bid? And are the only required docs with this bid the bid bond, addendum acknowledgment, and the personal property affidavit? Or are there other things required that just aren't listed?

The forms included in Exhibit 2 shall be submitted with the bid per Articles 27 – 30 of the Instructions to Bidders.

Question #11 – What is the depth of the Blue Grass Farms Pump Station?

Based on the Owner's record plans, the Blue Grass Farms Pump Station is approximately 20-feet deep as measured from the top slab to the invert of the wet well.

RECEIPT OF THIS ADDENDUM MUST BE ACKNOWLEDGED ON PAGE C-410 - 1 OF THE BID.